

- **1-5: Floor Structure**
 1. 2x6 Pressure Treated (PT) Sill Plate with Sill Seal
 2. 2x10 KD Joists and Girders (#2 Grade or Better)
 3. 3/4" Advantech Subfloor
 4. 2x8 PT Porch/Deck Floor Joists, Sills, and Headers (#2 Grade or Better)
 5. 5/4" Cedar Decking (Trex available)
- **6-9: Exterior Log Structure**
 6. Timeless Original 6x6 White Cedar Wall Logs. Foam Gasket, Caulking, Splines, and Fasteners included. Optional log sizes available.
 7. Window and Door Bucks at all Log Wall Openings
 8. White Cedar Siding and Pre-Cut False Log Corners for Dormer (if framed and sided), Floor Framing and Deck Skirting
 9. Square or Round Wall Bracing/Support Posts with Hardware as Needed
- **10-14: Interior Partitions and Loft Framing Structure**
 10. 2x4/2x6 KD Partition Framing Throughout
 11. 1x6 T&G Pine Partition Paneling Throughout
 12. 1x4 Pine Trim Boards
 13. #1 Grade 4x8/6x8 or Round Timber Ceiling Joists with Optional Hangers
 14. 2x6 T&G Spruce Loft Flooring
- **15-27: Roof Structure**
 15. Square or Round Pre-Cut Purlins
 16. Square or Round Log Trusses (Square trusses come pre-cut with optional hardware)
 17. 1x6 T&G Pine Paneling First Roof Deck
 18. 15# Felt Paper to cover Pine
 19. Foil Faced Foam Insulation (4" standard with optional upgrades)
 20. 1x3 Strapping 16" o.c. spanning two directions for proper ventilation
 21. 5/8" Zip System Roof Sheathing with Tape
 22. Architectural Roof Shingles with Drip Edge, Ridge Vent, and Cap
 23. 1x10/1x4 Pine Fascia and Frieze Board
 24. 4x8 Timber Rafters over Porch
 25. 1x6 T&G Pine First Roof Layer over Porch
 26. 5/8" Zip System Roof Sheathing with Tape over Porch
 27. 2x Conventional Rafters and/or Pre-Manufactured Trusses (not shown) are optional
- **28-32: Windows & Doors**
 28. Andersen 400 Series Windows with Screens and Hardware

29. Andersen 400 Series Gliding and/or French Doors with Screens and Hardware

30. Pre-hung Fiberglass and/or Steel Exterior Doors with Lock Sets

31. Pre-hung Solid Six-Panel Pine Interior Doors with Hardware

32. All Interior/Exterior Window and Door Trim (Interior Pine, Exterior Cedar)

- **33-35: Miscellaneous Materials**

33. Stair Systems to Loft and Basement using Square/Round Timbers or Conventionally Framed with Southern Yellow Pine Treads

34. Square or Round Railings at Loft, Stairs, Decks, and Porches

35. Square or Round White Cedar Porch Posts with Optional Posts to Grade at Daylight Basement per plans



1-4: Insulation Package

1. Modern Rustic Solid Log Wall
2. Foil Faced Insulation (1/2"-2" options)
3. 1x3 Strapping at 16" o.c.
4. 1x6 T&G Cedar Paneling (optional 1x8 T&G Pine)

